BRUHAT BENGALURU MAHANAGARA PALIKE

Name of Work: Maintenance and repairs of Footpath in Chowdeshwari Ward no-02 of Yelahanka Sub Division

Modified Schudule-B

Sl No	Description of work	Unit	Qty	Rate	Rs in Words
1	Removing and resetting of Kerb Stone	Sqm	579.00	96.05	Rupees Ninety Six And Paise Five Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	14.00	4548.45	Rupees Four Thousand Five Hundred Forty Eight And Paise Forty Five Only
3	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) 600 x 300 x 150 mm Kerb Stone	Nos	1556.00	380.25	Rupees Three Hundred Eighty And Paise Twenty Five Only
4	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	Sqm	447.65	70.13	Rupees Seventy And Paise Thirteen Only
5	Providing and fixing precast reinforced cement concrete covering slabs of 10Cm thick made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work	Sqm	124.20	1554.00	Rupees One Thousand Five Hundred Fifty Four Only
6	Providing and fixing precast reinforced cement concrete covering slabs of 23Cm thick made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work	Sqm	0.00	3777.75	Rupees Three Thousand Seven Hundred Seventy Seven And Paise Seventy Five Only
7	Hydraulic Excavator of 0.9 Cum Bucket	Hr	36.00	708.00	Rupees Seven Hundred Eight Only
8	1024 - Providing Tractor 40 HP Hire Charges of including Operator and Fuel	Day	135.00	966.00	Rupees Nine Hundred Sixty Six Only
9	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	1080.00	486.22	Rupees Four Hundred Eighty Six And Paise Twenty Two Only
10	Supply and fixing of Retro Reflective Single arrow road name sign board of size 1600mm x 900mm made out of retro reflective sheeting conforming to Type XI standards of ASTM D 4956 - 09 & as per IRC 67-2012 for full back ground of blue colour & white letters and fixed over 4 mm thick Aluminium Composite Material sheet having minimum 0.5 mm thick Aluminium skin on both sides with back side painted grey colour and fixed over back support frame SS angle of 15mm x 20mm x 1.2mm, supported by 38mm OD stainless steel pipe all round in 304 grade and 2 nos of vertical posts of 50 mm OD stainless steel pipe of 202 grade firmly fixed to the ground by means of properly designed foundation of size 450mm x 450mm x 600mm in 1:1.5:3 ratio cement concrete. The background shall be blue in color with letters and border in white, the item includes earthwork excavation, cost of all materials, loading, unloading, lead, lift, transportation etc.	Nos	4.00	28120.00	Rupees Twenty Eight Thousand One Hundred Twenty Only

	E1RL				
E1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work Loading and Unloading of Stone Boulder/Stone	Cum	813.00	266.35	Rupees Two Hundred Sixty Six And Paise Thirty Five Only
E2	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	T.km'	1040.64	84.11	Rupees Eighty Four And Paise Eleven Only

Executive Engineer
Yelahanka Division
BBMP

K-Sym.

10-1-23